

**REQUEST FOR PROPOSAL**

**Notice inviting tender for execution of work to Ancient remains at Bakshanagar, Shipahijala, Tripura, Archaeological Survey of India, Aizawl Circle, Mizoram**

**CRITICAL DATE SHEET**

01.	Date of issue of tender	24.01.2018
02.	Document download start date	25.01.2018
03.	Document download closing date	07.02.2018 upto 4.00 P.M.
04.	Submission of Tender date	08.02.2018 upto 2.00 P.M.
05.	Date of opening the tender	08.02.2018 upto 2.30 P.M.
06.	Validity date	65 days

*KI*  
01/02/2018  
Fok  
Dy. Superintending Archaeologist (I/C)

**TENDER FOR EXECUTION OF WORK**

**Price of Tender Rs. 500/-**

The Superintending Archaeologist, Archaeological Survey of India, Aizawl circle, Aizawl, on behalf of the President of India, Invites item rate tender in sealed cover from the approved contractors/suppliers who have past two years experience in similar civil work in **Heritage Building of Archaeological Survey of India**, for execution of work **SR(IP) to Ancient remains at Bakshangar, Shipahijala (2017-18** as per detailed below upto **14.00 hours of 08.02.2018** which will be opened on the same day at **14.30 hours** in the Office of the Superintending Archaeologist, Archaeological Survey of India, Aizawl Circle, Aizawl Circle, T-126, Tuikhualhang, Aizawl, Mizoram-796001

**Memorandum :-** i) **Earnest Money : Rs. 47,200/-** Demand Draft No.....

ii) **Security Deposit : Rs. 1,25,382/-** made up as under :

**Estimated Cost : Rs. 23,57,638.00**

**Schedule of Quantities of work**

Date of opening of Tender 08.02.2018

Item No.	Description or specification of work to be executed	Quantity of work	Places at which to be executed	Dates by which execution at all places must be completed	Rate at which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer)
1.	Provision for taking out damage and out of plumb ancient structure carefully without disturbing the adjacent structure/members and cleaning useable Ancient bricks etc.	48.45 cum	Work at site	Work to be completed by 65 days		Per Cum	
2.	Providing Lime concreting in Lime mortar on top of Ancient structure no I in 1:2:4 (1 lime : 2 surkhi : 4 brick aggregate 20 mm nominal size).	2.93 cum	-do-	-do-		Per Cum	
3.	Restoration of Ancient structure 30% old and 70% new special size bricks (25x4cm) in 1:1:1 (1 lime : 1 brick surkhi : 1 coarse sand) very carefully & maintain originality.	35.22 cum	-do-	-do-		Per Cum	

4.	Pointing and filletting over the Ancient structure in 1:1:1 ( 1 Lime : 1 Brick surkhi : 1 coarse sand).	367.65 sqm	-do-	-do-		Per Sqm.
5.	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, ramming with wooden or steel rammer for the construction of approach pathway and filling up ground depressions, lead upto 50 m and lift upto 1.5 m. All kinds of soil.	22.48 cum	-do-	-do-		Per Cum
6.	Providing and laying in position cement concrete (PCC) for base of approach pathway, of specified grade excluding the cost of centering and shuttering- All work up to plinth level in 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	22.60 cum	-do-	-do-		Per Cum
7.	Brickwork with common burnt clay Modular bricks of class designation 7.50 in foundation and plinth in 1:4 (1 cement : 4 sand).	74.59 cum	-do-	-do-		Per Cum
8.	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete. Mild steel and Medium Tensile steel bars.	1852.35 Kg.	-do-	-do-		Per Kg.
9.	Centering & shuttering including strutting propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts.	188.80 sqm	-do-	-do-		Per Sqm.
10.	Reinforced cement concrete work in 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillers, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement.	19.66 cum	-do-	-do-		Per Cum
11.	20 mm cement plaster inner and outer surface of the compound wall, RCC pillars etc. complete in 1:4 (1 cement : 4 fine sand).	334.68 sqm	-do-	-do-		Per sqm
12.	Provision for fitting and fixing of old M.S. grill after repairing etc.	15 nos.	-do-	-do-		Per Unit
13.	Supplying & Stacking at site of stone aggregate of 63 mm to 45 mm size.	6.29 cum	-do-	-do-		Per Cum

14.	Laying Spreading & compacting stone aggregate of specified size, hand picking ramming for proper compaction as directed by Engineer-in-charge.	6.29 cum	-do-	-do-		Per Cum
15.	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm.	54.55 sqm	-do-	-do-		Per sqm
16.	Finishing walls with Acrylic smooth exterior paint of required shade. New work (Two or more coat applied @ 1.67 ltr./10 sqm. Over and including priming coat of exterior primer applied @ 2.20 Kg./10 sqm.	1754.04 sqm	-do-	-do-		Per sqm
17.	Finishing with Deluxe Multi surface system for interiors and exteriors using Primer as per manufacturer.	909.56 sqm	-do-	-do-		Per sqm

• **Workers engaged for the work by contractor are to be paid as per minimum wages act of central Government.**


Tenders of the contractors/suppliers who will not deposit earnest money **Rs. 47,200/- (Rupees Forty Seven Thousand and Two Hundred Only)** vide **Demand Draft from any Nationalized Bank in favour of the "Superintending Archaeologist, Archaeological Survey of India, Aizawl Circle, Aizawl"** and copies of the **Registration Certificate (PWD/CPWD/MES) and Labour registration, Pan Card, latest Income tax clearance certificate/Vat clearance** as per notification of Directorate of commercial taxes, Mizoram/Tripura, shall be summarily rejected. The competent authority reserves the right to accept or reject any or all tenders without assigning any reasons thereof.

All tender forms downloaded from Archaeological Survey of India Website shall be accepted only if the tender form cost is remitted while submitting the tenders. Cost of Tender Form Rs.500/- (non refundable).

In case of public holiday declared on the opening date of Tender the same would be opened on the next working day.

**CONTRACTORS/SUPPLIERS MUST SUBMIT THE TENDERS DIRECTLY TO THIS OFFICE IN PERSONS OR BY POST WITHIN THE STIPULATED DATE.**

Supply of materials should be completed within **65 days** from the date of issue of work order.

  
 Dy. Superintending Archaeologist(I/C)  
 For

**N.B. : Quantity of work and materials may be increased/ decreased at site**

Contractor's Signature With Seal