

TENDER NOTICE

On behalf of the President of India, the Superintending Archaeologist, Archaeological Survey of India, Agra Circle, Agra invites sealed item rate tender for complete Job work from Archaeological Survey of India registered contractor including registration is essential of labour in ESI, PPF & labour commissioner.

The terms and condition and form of tender can be had from the office of the Superintending Archaeologist, Archaeological Survey of India, 22, Mall Road, Agra on all working days on payment of Rs. 500/- for each tender documents (not refundable) up to 16.00hrs on 19.08.2010 on production of Income Tax Permanent Account Number. The tender will be received up to 15.00hrs. on 20.08.2010 and will be opened at 15.15hrs. on the same date.

Name of Work	Description of item to be execute	Total Quantity to be execute	Estimated Cost	Earnest Money	Period of completion of work	Cost of Tender Form
Conservation of boundary wall (Forecourt) at Itimad-ud-daulla, Agra	Providing & laying in position cement concrete of specified grade in 1:2:4 (1 cement:2 C. sand stone aggregate 20mm nominal size) including supply of all material labours T&p etc. required for proper completion of work.	6.80 Cum.	4,59,744.00	11,494.00	180 days	Rs. 500.00
	Provision of electric installations as per site requirement (Staff Quarter) Two rooms, Two kitchens Two bath rooms and galleries etc. Details enclosed.	One Job				
	Providing & fixing Sanitary items complete as per site requirement (Staff Quarter) Two Kitchens, Two bathrooms and two Toilets etc.	One Job				
	Providing & fixing 1 HP submersible pump (Crompton/Baruna) fitting and boring of 5" dia PVC pipe 6 Kg/per cm.sqr and 32mm dia 6.15 B class with starter/panel up to 160 fit depth complete with all sanatory fittings of bathroom/toilet etc connected with water tank for proper supply of water Details enclosed.	One Job				
	White washing with lime on new work (Three or more coats) to give an even shade.	226.90 Sqm.				
	Distempering with 1 st quality acrylic Washable readymade distemper of approved brand and manufacture (Two or more coats) to give an even shade on new works with sand papering and fillings etc.	120.64 Sqm				
	Finishing of wall with waterproofing cement paint snowcem plus of approved brand on new work (two or more coats of required shade, sand papering and fillings etc.	106.26 Sqm				
	Providing & fixing glass panes with wooden fillets wherever necessary with float glass panes of thickness of 4mm complete.	5.60 Sqm.				
	Providing & fixing 37 mm (1.25') thick plain shutters door including MS nut hinges and alldrop with margin etc.	13.68 Sqm				
	Providing & fixing 0.75mt high MS grill fencing on low height boundary wall (Forecourt) of required design made of (40x40x5)mm angle iron frame with 10mm square bars having 10cm. spikes at top placed at 10cm. center to center brought to required shape including fifying with Nut-bolts & embodied in lime concrete block. Required for proper completion of work. For stopping and jumping of bad elements of surrounding area of monument. Drawing enclosed.	218.70 Sqm				
	Painting with synthetic enamel paint of approved brand and manufacture two or more coats on new M.S. grill work under the coat of suitable shade with approved brand and Manufacture to give an even shade.	109.35 Sqm				
Providing & fixing 1 st class ceramic glazed wall tiles conforming to IS:15622 of approved make in skirting over 12mm thick bed of cement mortar 1:3 (1 Cement:3 C. Sand) and jointing with grey cement mixed with pigment of matching shade complete.	43.92 Sqm.					

Superintending Archaeologist

