

ARCHAEOLOGICAL SURVEY OF INDIA

Name of work: **SR(P) Se' Cathedral, Old Goa -2010-11**

Date of tender opening: **12.08.2010**

Price of Tender : **Rs. 550/-**

TENDER FOR THE EXECUTION OF WORK

P.W.D- 9 (Tender)

I/We hereby tender for the supply for the President of India the materials described in the under mentioned memorandum according to the specification within the times specified therein subject to the conditions of the contract:-

- MEMORANDUM-
- (i) Earnest Money **2.5% Rs. 10116.00**
 - (ii) Security Deposit..... **Rs.**
 - (a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender **Rs.....**)
 - (b) Percentage to be deducted from bill **2.24% Income Tax**

Description or specification of materials to be supplied	Total quantities of each to be supplied	Places at which to be delivered	Quantities to be delivered at each place	Dates by which delivery at all places must be completed	Rates at which articles are to be supplied inclusive of every demand	Unit	Total cost of each article inclusive of every demand	Remarks
1	2	3	4	5	6	7	8	9
(Annexure enclosed)		Se' Cathedral, Old Goa		90 days				

*This percentage, where no security deposit is taken, will vary from 5% to 10% according to the requirements of the case. Where security deposit is taken see not to clause 1 of conditions of

ARCHAEOLOGICAL SURVEY OF INDIA GOA CIRCLE, GOA

Sl. No	Description	Qty	Rate	Amount	Remark
01	Provision for dismantling the old Mangalore tiled roof at south side over the blessed sacrament with battens including stacking of serviceable materials & disposal of unserviceable materials up to lead 50m etc complete.	306.00 Sqm			
02	Provision for relaying of removed Mangalore tiled roof by using the 50% new & 50% old rafters of size 5X10 cm at 50 cm C/c, 40% new Mangalore tiles and 60% of old tiles, 50% of new beam of size 15X8 cm including cutting, fixing, erection & dismantling of scaffolding after completion of work etc complete	306.00 Sqm			
03	Provision for providing new Mangalore tiled roof at south side by using new rafter of size 5X10cm at 50cm/c matti wood reepers of size 5X2.5cm over new beam of size 8.0 X15cm including cutting, fixing, erection & dismantling of scaffolding after completion of work etc complete.	83.64 Sqm			