

RCHAEOLOGICAL SURVEY OF INDIA

Name of work: **SR(P) Se'Cathedral, Old Goa -2010-11**

Date of tender opening: **12.08.2010**

Price of Tender : **Rs. 550/-**

TENDER FOR THE EXECUTION OF WORK

P.W.D- 9

(Tender)

I/We hereby tender for the supply for the President of India the materials described in the under mentioned memorandum according to the specification within the times specified therein subject to the conditions of the contract:-

MEMORANDUM- (i) Earnest Money **2.5% Rs. 4239 .00**

(ii) Security Deposit..... **Rs.**

(a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender **Rs.....**

(b) Percentage to be deducted from bill **2.24% Income Tax**

Description or specification of materials to be supplied	Total quantities of each to be supplied	Places at which to be delivered	Quantities to be delivered at each place	Dates by which delivery at all places must be completed	Rates at which articles are to be supplied inclusive of every demand	Unit	Total cost of each article inclusive of every demand	Remarks
1	2	3	4	5	6	7	8	9
(Annexure enclosed)		Se'Cathedral, Old Goa		90 days				

*This percentage, where no security deposit is taken, will vary from 5% to 10% according to the requirements of the case. Where security deposit is taken see not to clause

ARCHAEOLOGICAL SURVEY OF INDIA, GOA CIRCLE, GOA

Sl. No	Description	Qty	Rate	Amount	Remarks
01	Prov. for dismantling the steel work in built up Sections in angles, flats including all gusset plate, nut excluding cutting, dismembering & stacking in 50m lead for reuse etc complete.	14.42 Qtl			
02	Provision for refixing the old steel trusses & framed work after reducing space between each truss by providing new gusset plate, nut & bolt & fixing in PCC 1:2:4 and applying a priming coat of red lead etc complete	14.42 Qtl			
03	Provision for providing new steel trusses and framed work by using angles and gusset plate including cutting, welding, hoisting, fixing in position & applying priming coat of red lead paint etc. complete	12.08 Qtl			
04	Prov. for dismantling old, damaged GI Sheet gutters by cutting with gas cutter, removing old iron brackets manually and stacking the material at store room by head load.	1 Unit			
05	Provision for providing GI sheet gutters (trapezoidal shape) with three sides length of 0.60m, fixing at the roof of blessed sacrament at eave board level for draining out rain water including fixing of M.S flat angle (bracket)for support of gutters & priming coat etc. complete.	58 Rmt			