

## ARCHAEOLOGICAL SURVEY OF INDIA

Name of work: **SR(P) Se' Cathedral, Old Goa -2010-11**

Date of tender opening: **12.08.2010**

Price of Tender : **Rs. 600/-**  
(Tender)

### TENDER FOR THE EXECUTION OF WORK

P.W.D- 9

I/We hereby tender for the supply for the President of India the materials described in the under mentioned memorandum according to the specification within the times specified therein subject to the conditions of the contract:-

MEMORANDUM- (i) Earnest Money **2.5% Rs. 21674 .00**

(ii) Security Deposit..... **Rs.**

(a) Payable immediately on the acceptance of tender (including earnest money if deposited in cash with tender **Rs.....**)

(b) Percentage to be deducted from bill **2.24% Income Tax**

Description or specification of materials to be supplied	Total quantities of each to be supplied	Places at which to be delivered	Quantities to be delivered at each place	Dates by which delivery at all places must be completed	Rates at which articles are to be supplied inclusive of every demand	Unit	Total cost of each article inclusive of every demand	Remarks
1	2	3	4	5	6	7	8	9
(Annexure enclosed)		<b>Se' Cathedral, Old Goa</b>		<b>90 days</b>				

\*This percentage, where no security deposit is taken, will vary from 5% to 10% according to the requirements of the case. Where security deposit is taken see not to claus

## ARCHAEOLOGICAL SURVEY OF INDIA GOA CIRCLE, GOA

Sl. No	Description	Qty	Rate	Amount	Remark
01	Prov. for providing new Mangalore tiled roof at North & South side by using new rafter of size 5X10cm, new matti wood reepers of size 2.5 X 5.0cm over new I beam ISWB150 @17kg/m including cutting, welding, fixing, erection & dismantling of scaffolding after completion of work etc. complete	462.51 Sqm			
02	Prov. for applying wood preservative paint two coats over wooden roofing work etc complete.	213.00 Sqm			
03	Prov. for construction of laterite stone pillar at North side for resting the roof beam over it to maintain equal level of the new roof including dressing & curing etc. complete	3.60 Cum			
04	Prov. for Providing plastering of 12mm thick to the pillar in CM1:3 (1cement:3sand) finishing and curing etc. comp	24.36 Sqm			