

**F.No. M3/Web-Tender/11-12/
Government of India
Office of the Superintending Archaeologist.
Archaeological Survey of India
Kolkata Circle, Kolkata.**

**FILLED UP FORMAT OF LIMITED TENDER FOR CIRCULATION THROUGH
WEBSITE OF THE ARCHAEOLOGICAL SURVEY OF INDIA**

Sl. No	Name of Office	District/ State	Title of Work	Last date for sale & submission.
1.	Archaeological Survey of India Kolkata Circle , Kolkata.	Bishnupur , Bankura, West Bengal	Execution of work to Sareswar & Saileswar Temple, Bishnupur, Bankura.	Last date for sale 23.01.2012 before 16.00 hrs & last date of submission 25.01.2012 up to 14.00hrs. Last date of application for tender 23.01.2012.

Sl.No.	Name of materials	Quantity	Estimated Amount
1.	Provision for deep boring with submersible pump including fitting fixing complete.	One item	111500=00
2.	Earthwork in excavation of foundation trenches within a lead of 75 mt as directed.	20.44cum	2420=00
3.	Single brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	27.48sqm	5911=00
4.	Ordinary cement concrete M15 (4:2:1)with graded stone chips (20 mm down Pakur Varity) excluding shuttering and reinforcement in foundation complete	3.26cum	14892=00
5.	Ist class brickwork with modern bricks in sand and cement Mortar (1:4), 1 Cement : 4 sand according to drawings in foundation and plinth curing complete.	31.28cum	118004=00
6.	25mm thick plaster to wall, floor with (1:4) cement :sand mortar including rounding off corners complete.	110.2sqm	14715=00
7.	Neat cement punning about 1.5 mm thick in wall, floor etc	67.45sqm	1911=00
8	35 mm thick artificial stone flooring with cement concrete (1:2:4) cement: sand: ¼ th stone chips with 3mm thick neat finish on top	7.5 sqm	1933=00

9.	Fitting fixing of diferent materials in toilet block 2 nos water closet Indian type 20rft CI pipe 1" GI pipe 50 rft 2 x500 litre sintex double coated PVC tank 2 nos bib cock 2 nos PVC door (3 ft x 6 ft) with PVC frame Tower bolt / Hing / Hatch bolt 2' & 4 " GI Bends / tee & CI bends as required Electric wire 4 coil Electric board / fuse / switch / light fittings as required	One item	27800=00
Total			Rs. 2,99,086.00

E.M.D. Rs. 7,500/-

****Applications invited from the approved contractors/suppliers having last two years experience of work in Heritage building for specific items/materials.**

- Workers engaged for the work by contractor are to be paid as per minimum wages act of central Government.**

SUPERINTENDING ARCHAEOLOGIST