

REQUEST FOR PROPOSAL

Notice inviting tender for execution of work to Ancient mound called Pujakhola at Pachim Pilak, Tripura, Archaeological Survey of India, Aizawl Circle, Mizoram

CRITICAL DATE SHEET

01.	Date of issue of tender	24.01.2018
02.	Document download start date	25.01.2018
03.	Document download closing date	07.02.2018 upto 4.00 P.M.
04.	Submission of Tender date	08.02.2018 upto 2.00 P.M.
05.	Date of opening the tender	08.02.2018 upto 2.30 P.M.
06.	Validity date	65 days

St
01/02/2018
Dy. Superintending Archaeologist (I/C)
F012

TENDER FOR EXECUTION OF WORK

Price of Tender Rs. 500/-

The Superintending Archaeologist, Archaeological Survey of India, Aizawl circle, Aizawl, on behalf of the President of India, Invites item rate tender in sealed cover from the approved contractors/suppliers who have **past two years experience in similar civil work in Heritage Building of Archaeological Survey of India**, for execution of work **SR(P) to Ancient mound called Pujakhola at Pachim Plak, Tripura** (2017-18 as per detailed below upto **14.00 hours of 08.02.2018** which will be opened on the same day at **14.30 hours** in the Office of the Superintending Archaeologist, Archaeological Survey of India, Aizawl Circle, Aizawl Circle, T-126, Tulkhuahiang, Aizawl, Mizoram-796001.

Memorandum :- i) Earnest Money : Rs. 35,200/-

Demand Draft No.....

ii) Security Deposit : Rs. 95,499/-

made up as under :

Estimated Cost : Rs. 17,59,977.00

Schedule of Quantities of work

Date of opening of Tender 08.02.2018

Item No.	Description or specification of work to be executed	Quantity of work	Places at which to be executed	Dates by which execution at all places must be completed	Rate At which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer)
1.	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 mm in depth, breaking clods, watering, ramming with wooden or steel rammer and dressing up for the retaining wall and filling up ground depressions, lead up to 50 m and lift up to 1.5 m. All kinds of soil.	3.00 cum	Work at site	Work to be completed by 65 days		Per Cum	
2.	Provision for scientific clearance of the mound very carefully and slowly without disturbing the Ancient structure.	652.5 cum	-do-	-do-		Per Cum	
3.	Provision for taking out decayed, damaged, deteriorated Bricks from structure carefully without disturbing adjacent structure/member & cleaning useable Ancient bricks etc.	36.00 cum	-do-	-do-		Per Cum	

4.	Restoration of Ancient structure with special size bricks (25x17x4 cm) pin 1:1:1 (1 lime : 1 brick surkhi : 1 sand) from foundation level to a height of 3.00 m of Ancient structure.	36.00 cum	-do-	-do-		Per Cum	
5.	Steel reinforcement for RCC work for construction of pedestral and base pillar of Sculpture shed.	187.75 Kg.	-do-	-do-		Per Kg.	
6.	Providing and laying in position cement (P.C.C.) concrete of specified grade excluding the cost of centering and shutterin- All work up to plinth level in 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.44 cum	-do-	-do-		Per Cum	
7.	Centering & shuttering including strutting propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and struts.	13.06 sqm	-do-	-do-		Per Sqm.	
8.	Providing and Laying in position specified grade of Reinforced cement concrete (RCC) excluding cost of centering, shuttering, finishing and reinforcement in 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	3.64 cum	-do-	-do-		Per Cum	
9.	920 mm cement plaster of the padastral & pillar surface in mix 1:4 (1 cement : 4 fine sand).	10.56 sqm	-do-	-do-		Per Sqm.	
10.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.	376.59 Kg.	-do-	-do-		Per Kg.	
11.	Providing and fixing pre-coated galvanized iron profile sheets (size shape and pitch of corrugation as approved by Engineer-in-charge) 0.50mm + 0.50%, total coated thickness with zinc coating 120 gsm as per IS:277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length up to 12 meter or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55 mm) with EPDM seal complete up to any pitch in horizontal/ vertical or curved surfaces excluding the cost of purling, rafters and trusses and including cutting to size and shape wherever required.	21.16 sqm	-do-	-do-		Per sqm	

12.	Providing and fixing pre-coated galvanized steel sheet roofing accessories 0.50 mm (+ 0.50%) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws complete upto 600 mm.	13.00 mtr	-do-	-do-		Per mtr
13.	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting steel work with Deluxe Multi surface paint to give an even shade. Two or more coat applied @ 0.80 ltr/10 sqm of approved brand and manufacture.	10.48 sqm	-do-	-do-		Per Sqm.

Workers engaged for the work by contractor are to be paid as per minimum wages act of central Government.

Tenders of the contractors/suppliers who will not deposit earnest money **Rs. 35,200/- (Rupees Thirty Five Thousand and Two Hundred Only) vide Demand Draft from any Nationalized Bank in favour of the "Superintending Archaeologist, Archaeological Survey of India, Alzawl Circle, Alzawl"** and copies of the **Registration Certificate (PWD/CPWD/MES) and Labour registration, Pan Card, latest Income tax clearance certificate/Vat clearance** as per notification of Directorate of commercial taxes, Mizoram/Tripura, shall be summarily rejected. The competent authority reserves the right to accept or reject any or all tenders without assigning any reasons thereof.

All tender forms downloaded from Archaeological Survey of India Website shall be accepted only if the tender form cost is remitted while submitting the tenders. Cost of Tender Form Rs. 500/- (non refundable).

In case of public holiday declared on the opening date of Tender the same would be opened on the next working day.
CONTRACTORS/SUPPLIERS MUST SUBMIT THE TENDERS DIRECTLY TO THIS OFFICE IN PERSONS OR BY POST WITHIN THE STIPULATED DATE.
 Supply of materials should be completed within **65 days** from the date of issue of work order.


 31/01/2018
 Dy. Superintending Archaeologist(I/C)

N.B. : Quantity of work and materials may be increased/ decreased at site

Contractor's Signature with Seal