

**REQUEST FOR PROPOSAL**

**Notice inviting tender for execution of work to Sculptures and rock-cut relief at Unakotitirtha,  
Unakoti , Tripura, Archaeological Survey of India, Aizawl Circle, Mizoram**

**CRITICAL DATE SHEET**

01.	Date of issue of tender	25.01.2018
02.	Document download start date	26.01.2018
03.	Document download closing date	14.02.2018 upto 4.00 P.M.
04.	Submission of Tender date	15.02.2018 upto 2.00 P.M.
05.	Date of opening the tender	15.02.2018 upto 2.30 P.M.
06.	Validity date	180 days

*St*  
01/02/2018  
Dy. Superintending Archaeologist (I/C)  
*For*

**TENDER FOR EXECUTION OF WORK**

**Price of Tender Rs. 1000/-**

The Superintending Archaeologist, Archaeological Survey of India, Aizawl circle, Aizawl, on behalf of the President of India, Invites item rate tender in sealed cover from the approved contractors/suppliers who have **past two years experience in similar civil work in Heritage Building of Archaeological Survey of India**, for execution of work **SR(P) to Sculptures and rock-cut relief at Unakotitirtha, Unakoti** as per detailed below upto **14.00 hours of 15.02.2018** which will be opened on the same day at **14.30 hours** in the Office of the Superintending Archaeologist, Archaeological Survey of India, Aizawl Circle, Aizawl Circle, T-126, Tuikhualhang, Aizawl, Mizoram-796001.

**Memorandum :- i) Earnest Money : Rs. 1,88,000/- Demand Draft No.....**

**ii) Security Deposit : Rs. 4,76,475/- made up as under :**

**Estimated Cost : Rs. 93,79,482.00**

Schedule of Quantities of work

Item No.	Description or specification of work to be executed	Quantity of work	Places at which to be executed	Date of opening of Tender 15.02.2018 Dates by which execution at all places must be completed	Rate At which the item of work to be executed (inclusive of all demand to be quoted by Tenderer)	Unit	Total cost of each works (inclusive of all demand to be quoted by Tenderer)
1.	Demolishing damage R.C.C. railing and post manually including disposal of dead materials, within 50 metres leas as per direction of Engineer-in-charge.	21.39 cum	Work at site	Work to be completed by 180 days		Per Cum	
2.	Earth work in rough excavation, for both side guard wall of the approach pathway, railing post and R.R. masonry wall, dry stone masonry wall etc.	235.16 cum	-do-	-do-		Per Cum	
3.	Providing and laying in position cement (P.C.C) concrete of specified grade excluding the cost of centering and shuttering at base of guard wall of approach pathway, dry stone masonry wall, R.R. maonary wall and railing post for hand rail and view point shade- All work up to plinth level in	99.62 cum	-do-	-do-		Per Cum	

	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).						
4.	Coursed rubble stone (25x20x15 cm) masonry with hard stone for guard wall both side of the pathway/steps in Cement mortar 1: 6 (1 cement : 6 coarse sand)	162.84 cum	-do-	-do-		Per Cum	
5.	Providing stone slab (size 10x10x10 cm) and above the pathway/steps in cement mortar 1:4 including filling up the joints with neat cement slurry (Calculation for 10 sqm x 0.10 = 1.00 cum).	831.80 Sqm	-do-	-do-		Per Sqm.	
6.	Providing and fixing G.I. hand rail of approved size by welding etc. to steel ladder railing, staircase railing and similar works, including applying priming coat of approved steel primer.	16400.00 Kg.	-do-	-do-		Per Kg.	
7.	Providing dry dressed stone wall for protection of the eroded bank of channel/back side of big Shiva head.	48.00 cum	-do-	-do-		Per Cum	
8.	Providing and fixing of RCC pipe NP2 class 450 mm dia 6 mtr (4.1x1.50 = 6.0 mtr. Wastage 10% = 0.60 mtr. total 6.60 mtr)	6.60 mtr	-do-	-do-		Per mtr	
9.	Debris clearance of the Shanvunath area and left side towards hirimba hirimbi pathway.	92.00 cum	-do-	-do-		Per Cum	
10.	Providing and fixing precast galvanized iron profile sheets (size shape and pitch of corrugation as approved by Engineer-in-charge) 0.50mm + 0.50%, total coated thickness with zinc coating 120 gm as per IS:277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length up to 12 meter or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55 mm) with EPDM seal complete up to any pitch in horizontal/ vertical or curved surfaces excluding to size and shape wherever required.	21.16 sqm	-do-	-do-		Per sqm	

11.	Providing and fixing pre-coated galvanized steel sheet roofing accessories 0.50 mm (+ 0.50%) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws complete upto 600 mm.	13.00 mtr	-do-	-do-		Per mtr
12.	Supplying and fixing in position of decorative cast iron benches of length 1.50 m made of cast iron in both side with arm and rectangular M.S. pipe in sitting and back portion fixing with P.C.C. 1 : 2 : 4 platform of size 1.80x1.50x0.10 m for sitting facilities to the visitors including priming coat and S.E. point.	10. nos.	-do-	-do-		each
13.	Providing fitting and fixing solar light (11 watt) including all accessories to illuminate the monument complex at Urakati.	5 nos.	-do-	-do-		each

• **Workers engaged for the work by contractor are to be paid as per minimum wages act of central Government.**

Tenders of the contractors/suppliers who will not deposit earnest money Rs. 1,88,000/- (Rupees One Lakh Eighty Eight Thousand Only) vide Demand Draft from any Nationalized Bank in favour of the "Superintending Archaeologist, Archaeological Survey of India, Aizawl Circle, Aizawl" and copies of the Registration Certificate (PWD/CPWD/MES) and Labour registration, Pan Card, latest Income tax clearance certificate/Vat clearance as per notification of Directorate of commercial taxes, Mizoram/Tripura, shall be summarily rejected. The competent authority reserves the right to accept or reject any or all tenders without assigning any reasons thereof.

All tender forms downloaded from Archaeological Survey of India Website shall be accepted only if the tender form cost is remitted while submitting the tenders. Cost of Tender Form Rs. 1000/- (non refundable).

In case of public holiday declared on the opening date of Tender the same would be opened on the next working day.

CONTRACTORS/SUPPLIERS MUST SUBMIT THE TENDERS DIRECTLY TO THIS OFFICE IN PERSONS OR BY POST WITHIN THE STIPULATED DATE.

Supply of materials should be completed within **180 days** from the date of issue of work order.

**N.B. : Quantity of work and materials may be increased/ decreased at site**

*RS*  
21/01/2018  
Dy. Superintending Archaeologist(I/C)  
For

Contractor's Signature with Seal